

RIGID CONCRETE SLAB INSERTS

STRAIGHT - MALLEABLE IRON



EF75



PART #	SIZE	MASTER QTY.
EF50	1/2"	10
EF75	3/4"	20
EF100	1"	10
EF125	1-1/4"	10

FEATURES

- Provides flush threaded conduit hub for mounting, pulling and future access to conduit system
- Permits prefabrication of in-slab conduit system
- EF50 and EF125 include rubber, plug gasket

APPLICATIONS

- For use with Cable Support Bodies
- Must be purchased with Cable Support Bodies (CSB5-CSB10)

STANDARD MATERIAL

- Malleable iron

CERTIFICATIONS

- UL Listed (EF50 only)

RIGID CONCRETE SLAB INSERTS

90° - MALLEABLE IRON



EFL50



PART #	SIZE	MASTER QTY.
EFL50	1/2"	10
EFL75	3/4"	20
EFL100	1"	10
EFL125	1-1/4"	10

FEATURES

- Provides flush threaded conduit hub for mounting, pulling and future access to conduit system
- Permits prefabrication of in-slab conduit system

APPLICATIONS

- Allows in-slab ceiling drops and floor mounts in poured concrete

STANDARD MATERIAL

- Malleable iron

CERTIFICATIONS

- cULus Listed (exception ELF125)